



ROOF SYSTEM

- 6/12 ROOF TRUSS – 24" O/C
- 1/2" O.S.B. w/ H-CLIPS
- 15# ROOF FELT
- FIBERGLASS SHINGLES
- R-38 INSULATIONS
- FULL RIDGE VENT
- 2 x 6 SPF#2 FACE BOARD w/ ALUM. FASCIA
- VENTED ALUM. SOFFIT
- ICE GUARD IN ALL VALLEYS AND ON EAVES OVER HEATED SPACES

TYPICAL INTERIOR NON-BEARING WALL CONSTRUCTION

- 2 X 4 SPF#2 w/ DBL. TOP PLATE
- SINGLE BOTTOM PLATE
- DBL. 2 X 4 HEADERS
- 1/2" GYPSUM BOARD 2 SIDES

EXTERIOR WALL CONSTRUCTION

- 2 x 6 SPF#2 STUDS – 16" O/C
- 2 x 6 SPF #2 PLATE (DOUBLE TOP/SINGLE BOTTOM)
- 2 x 10 SPF#2 HEADERS – AS REQ'D BY 2006 IRC
- 7/16" O.S.B. w/ HOUSE WRAP – ALL SHEETED AREAS
- 1/2" GYPSUM BOARD – INTERIOR
- R-19 KRAFT FACED INSULATION

NOTE:
TYPICAL DETAIL FOR CONSTRUCTION STANDARDS
& MATERIAL SPEC'S. REFERENCE ONLY